**Vendor:** Avixa

**Exam Code:** CTS

**Exam Name:** Certified Technology Specialist

**Version:** DEMO

**QUESTION 1**
Assuming a 10' (3 m) ceiling, what is the approximate volume of this room?




A. 300 cubic ft (8.5 m3)
B. 600 cubic ft (17 m3)
C. 1500 cubic ft (42.5 m3) o
D. 6000 cubic ft (162 m3)

**Answer:** D

**QUESTION 2**
The BEST way to ensure that a project is on budget is to

A. calculate the number of calendars days remaining to completion.
B. visit the job site and determine the percentage of work completed.
C. ask the installation team to estimate remaining work to completion.
D. review accrued labor and material costs against remaining work.

**Answer:** D

**QUESTION 3**
Maintaining AV operations includes which of the following?

A. conforming to DISCAS
B. measuring system SPL

C. updating control system firmware
D. comparing NAG and PAG calculations

**Answer:** C

**QUESTION 4**
How frequently should a personal fall arrest harness be inspected?

A. weekly
B. before each use
C. at the beginning of each project
D. at the beginning of each work day

**Answer:** B

**QUESTION 5**
The circuit on the RIGHT is an electrical drawing of what type of speaker system?



A. series circuit
B. constant voltage
C. stereo pair circuit
D. combination parallel/series circuit

**Answer:** D

**QUESTION 6**
When planning to use audio equipment on a converged enterprise network, it may be desirable to separate broadcast domains in order to

A. avoid audio feedback between devices.
B. avoid crosstalk between multi track channel packets.
C. avoid delaying time sensitive AV traffic on the network.
D. comply with local electrical and telecommunication regulations.

**Answer:** C

**QUESTION 7**
An application requires Its equipment to be operational 24 hours a day and the owner considers the system mission critical. What type of warranty would be BEST for the equipment?

A. limited warranty
B. implied warranty
C. manufacturer's factory warranty
D. advanced replacement warranty

**Answer:** D

**QUESTION 8**
A client has ordered a large project from a company. This project has several critical components and a fixed schedule. Which of the following will be VITAL for ensuring that the company meets the deadlines?

A. proper job costing
B. confirming lead times
C. qualifying the customer
D. confirming price changes

**Answer:** B

**QUESTION 9**
Before confirming an anticipated completion date with the customer, it is MOST important to

A. double check the floor finishes.
B. ensure the date is not a holiday.
C. ensure no components are backordered.
D. create the system maintenance schedule.

**Answer:** C

**QUESTION 10**
Which of the following is addressed within the Needs Analysis part of the AV Design process?

A. creating the project timeline
B. outlining project Bill of Materials
C. identifying key stakeholders for the project
D. identifying functional requirements of the project

**Answer:** D

**QUESTION 11**
What is the MAIN difference between OLED displays and LED displays?

A. luminosity
B. higher brightness
C. self-emitting light source
D. determined screen shape

**Answer:** C

**QUESTION 12**
During a site survey of a facility to be upgraded or modernized, it is important to check wireless microphones that may be redeployed to ensure

A. battery types conform to environmental concerns.
B. polar patterns will not clash with new fabric treatments.
C. microphones are operating on acceptable radio frequencies.
D. antenna design will not interfere with HDBaseT signal distribution system.

**Answer:** C

**QUESTION 13**
A client has ordered a large LED video wall to be installed in an existing board room. What should be the integrator's MAIN operational concerns?

A. power and temperature
B. brightness and contrast
C. aspect ratio and resolution
D. cable management and length

**Answer:** A

**QUESTION 14**
Assuming that the screen and projector are both Ethernet controllable devices, where does the control system for the AV solution need to exist?

A. connected to the network
B. in the rear projection room
C. in a dedicated rack in the room
D. above the projector, plugged into the serial port on the projector

**Answer:** A

# Thank You for Trying Our Product

## Lead2pass Certification Exam Features:

★ More than **99,900** Satisfied Customers Worldwide.

★ Average **99.9%** Success Rate.

★ **Free Update** to match latest and real exam scenarios.

★ **Instant Download** Access! No Setup required.

★ Questions & Answers are downloadable in **PDF** format and **VCE** test engine format.

★ Multi-Platform capabilities - **Windows, Laptop, Mac, Android, iPhone, iPod, iPad**.

★ **100%** Guaranteed Success or **100%** Money Back Guarantee.

★ **Fast**, helpful support **24x7**.

View list of all certification exams: http://www.lead2pass.com/all-products.html

**10% Discount Coupon Code:** **ASTR14**